



START START BND PROJECT COMPLETE
DEC 2020 DEC 2020 MAR 2021 APR 2021

MAVs deployed per day - average (238kWp) 18 MAVs deployed per day - top (612kWp) MAVs deployed per week - average (1.19MWp)Injuries Major Quality Incidents

WHY MAVERICK?

Energy Density

The land requirement for such a large project was a major consideration in its development. SA Water had limited space around their water processing facilities so a compact solution was needed. Leveraging an east-west configuration, MAVERICK produces more energy on less land - typically around 1.5 to 2 times the energy of traditional fixed tilt or tracking solar arrays. The Happy Valley project squeezes 12.8MW of solar capacity, or 33,750 panels, on just 12Ha of land - a utilisation factor of ~80%.



Ground conditions

The soil at the Happy Valley location had been recently labelled 'extremely reactive' after the clearing of a pine plantation weeks earlier. This would have significantly raised the installation cost and risk for a conventional solar array, however MAVERICK's ballasted nature limits ground penetrations and avoids excessive drilling and piling into the bedrock beneath the soil.



MAVERICK can easily be moved or readjusted for maintenance works or if ground movements exceed the anticipated levels.



